


# TYPE B



**NOTE:**

1. MAIN CHANNEL: CAPACITY TO BE NO LESS THAN 20% OF 100-YEAR AT MAIN CHANNEL DEPTH. MAXIMUM 100-YEAR FLOW VELOCITY IS 7 FPS.
2. TRICKLE CHANNEL: MINIMUM CAPACITY TO BE 1% TO 3% OF 100-YEAR FLOW BUT NOT LESS THAN 1 CFS. CHANNEL TO BE CONSTRUCTED OF CONCRETE, GROUTED RIPRAP OR OTHER MATERIALS APPROVED BY THE CITY ENGINEER. SEE FIGURE 400-16 FOR REQUIREMENTS IN SANDY SOILS.
3. NORMAL DEPTH: FLOW DEPTH FOR 100-YEAR FLOW SHALL NOT EXCEED 5 FEET.
4. FREEBOARD: FREEBOARD TO BE A MINIMUM OF 1 FOOT.
5. MAINTENANCE ACCESS ROAD: MINIMUM WIDTH TO BE 12 FEET. CITY MAY REQUIRE ALL OR PART OF THE ROAD TO BE SURFACED.
6. EASEMENT/ROW WIDTH: MINIMUM WIDTH TO INCLUDE FREEBOARD AND MAINTENANCE ACCESS ROAD.
7. OVERBANK: FLOW IN EXCESS OF MAIN CHANNEL TO BE CARRIED IN THIS AREA. AREA MAY BE USED FOR RECREATION PURPOSES.

N.T.S.



STANDARDS &  
SPECIFICATIONS

REVISED:

DATE:

DRAWING NO. 400-08

**TYPICAL  
GRASS LINED  
CHANNEL SECTION**