ELBERT COUNTY 2015 GRAVEL ROAD AND DRAINAGE IMPROVEMENT PROJECT

PROJECT NAME:	**2015 Gravel Rd & Drainage Improvement Project**	LENGTH:	1.5 miles	RIGHT OF WAY:	
COUNTY:	**ELBERT COUNTY**	CREATED:		BY	JSO
JOB NUMBER:		REVISED:		CHECKED:	
FILE NAME:		PRINTED:	22-Sep-15	REVISED:	

ROADWAY **Running Brook Road**

DESCRIPTION	*UNIT*	*APPROXIMATE QTY*	*UNIT PRICE*	*TOTAL AMOUNT*
Mobilization	LS	1	$27,445.40	$27,445.40
RECYCLED ASPHALT - FURNISH AND INSTALL (1.6 miles)	SY	22,000	$5.92	$130,240.00
RECYCLED ASPHALT - FURNISH ONLY (Stockpile Location - E bert County Fairgrounds)	CY	10,000	$31.15	$311,500.00
18" RCP (CLASS 3) @ DRIVEWAYS	LF	300	$55.29	$16,587.00
18" RCP (CLASS 4)	LF	300	$77.31	$23,193.00
RIPRAP (TYPE L, 18-INCH)	CY	350	$91.71	$32,098.50
FURNISH AND INSTALL CHECK DAMS	EA	20	$659.39	$13,187.80
SHAPE AND GRADE ROADSIDE SWALES	LF	1,500	$2.53	$3,795.00
FURNISH AND INSTALL SILT FENCE	LF	500	$3.75	$1,875.00
SEED AND MULCH DISTURBED AREAS	AC	5	$3,323.45	$16,617.25
TRAFFIC CONTROL	DAYS	20	$500.00	$10,000.00
Potholing / Utility Locates	LS	1	$2,500.00	$2,500.00

TOTAL CONSTRUCTION COST: **$589,038.95**

SIGNATURE LINE: Justin Lewis **DATE:** 22-Sep-15

DRAFT